

IRONWOOD OUTDOOR LIVING LLC

PROJECT ESTIMATE AND PROPOSAL

Prepared for: Jason Robert Kim and Sarah Kim
Property: 4417 Ridgewood Lane, Columbus, OH 43235
Project: Pergola Addition and Covered Patio Extension
Estimate Date: January 22, 2026
Estimate Valid Through: October 31, 2026
Estimate No.: IWL-EST-2026-0188
Prepared by: Kevin Marsh, Project Manager, Ironwood Outdoor Living LLC
Contractor Address: 5820 Stelzer Road, Columbus, OH 43219
Phone: (614) 555-7090
License: Ohio Contractor License No. OHL-2008-88041

PROJECT SCOPE

This estimate covers the design and construction of a freestanding cedar pergola attached to the existing rear covered patio at 4417 Ridgewood Lane, with extension of the concrete patio surface and installation of a new pergola structure, electrical rough-in for string lights, and a gas line stub-out for an outdoor kitchen connection. Work described is based on two site visits on January 10 and January 18, 2026, and customer discussions with Jason Kim.

SCOPE OF WORK BY LINE ITEM

Item	Description	Unit	Qty	Unit Price	Total
1	Demolition: remove existing patio pavers (12 x 16 ft area)	SF	192	\$4.50	\$864.00
2	Concrete patio extension: pour 4-inch slab with rebar (16 x 24 ft)	SF	384	\$12.50	\$4,800.00
3	Cedar pergola structure: 16 x 16 ft, 4 post, 8 beam, Douglas fir rafters	LS	1	\$8,200.00	\$8,200.00
4	Post footings: 4 x 16-inch diameter concrete footings, 36-inch depth	EA	4	\$385.00	\$1,540.00
5	Stain and seal: cedar pergola, two-coat oil-based stain, grey-brown	LS	1	\$1,100.00	\$1,100.00
6	Electrical rough-in: 20A circuit for string lights, 2 exterior outlets	LS	1	\$1,480.00	\$1,480.00
7	Gas stub-out: 3/4-inch black iron line from basement to patio, with shut-off	LS	1	\$1,850.00	\$1,850.00
8	Concrete sealer: apply penetrating sealer to full patio surface	SF	576	\$1.80	\$1,036.80
9	Cleanup and haul-off	LS	1	\$480.00	\$480.00
	Subtotal				\$21,350.80

PRICING SUMMARY

Item	Amount
Subtotal	\$21,350.80
Sales tax (Ohio, 7.5%)	\$1,601.31
TOTAL ESTIMATE	\$22,952.11

MATERIALS

All lumber is kiln-dried No. 1 grade Western Red Cedar unless otherwise noted. Concrete is 3,000 PSI minimum compressive strength, placed by pump truck. Stain is Cabot Australian Timber Oil in Honey Teak. Electrical work is per NEC 2020 and Ohio residential code. Gas line work includes pressure test and Franklin County inspection.

TIMELINE

Milestone	Target Date
Permit application submitted by contractor	October 15, 2026
Permit expected approval	October 30, 2026
Site mobilization and patio demolition	November 3, 2026
Concrete pour and footing work	November 5 to 7, 2026
Pergola framing and installation	November 10 to 14, 2026
Electrical and gas rough-in	November 17 to 18, 2026
Stain, seal, and final inspection	November 21, 2026
Final walkthrough and punch-list	November 24, 2026

PAYMENT SCHEDULE

Payment	Amount	Due Date
Deposit (25%) upon acceptance	\$5,738.03	Upon signing
Progress draw (50%) at concrete pour completion	\$11,476.06	November 7, 2026
Final payment (25%) at final walkthrough	\$5,738.02	November 24, 2026

TERMS AND CONDITIONS

This estimate is valid through the date noted above. Work is subject to Franklin County permit approval. Any changes to scope after acceptance will be priced in a written change order before work proceeds. Ironwood Outdoor Living LLC carries general liability insurance (\$2M per occurrence) and workers compensation coverage for all employees. A signed copy of this estimate along with the deposit constitutes acceptance. See x7.xlsx for the home maintenance log where this project will be tracked upon completion.

ACCEPTED BY HOMEOWNER

Jason Robert Kim

Date: _____

ACCEPTED BY CONTRACTOR

Kevin Marsh, Ironwood Outdoor Living LLC

Date: January 22, 2026

MATERIALS SPECIFICATIONS AND WARRANTY INFORMATION

Ironwood Outdoor Living LLC / Estimate IWL-EST-2026-0188 / 4417 Ridgewood Lane, Columbus, OH 43235

Cedar Lumber Specifications:

Item	Species / Grade	Source	Moisture Content	Treatment
Pergola posts (4x4)	Western Red Cedar, No. 1	Pacific Northwest mill-certified	19%	Natural; no treatment required
Pergola beams (2x8)	Western Red Cedar, No. 1	Pacific Northwest mill-certified	19%	Natural; no treatment required
Rafters (2x6)	Western Red Cedar, No. 1	Pacific Northwest mill-certified	19%	Two-coat oil stain, grey-brown
Decorative purlins	Western Red Cedar, Select	Pacific Northwest mill-certified	19%	Two-coat oil stain, grey-brown
Hardware	G185 hot-dip galvanized	Simpson Strong-Tie	N/A	Galvanized for exterior use
Concrete	3,000 PSI, air-entrained	Lafarge Columbus batch plant	N/A	Penetrating sealer applied after cure

Warranty Coverage:

Coverage Area	Duration	Terms
Labor and installation workmanship	2 years from final walkthrough	Covers defects in installation, not material degradation from weather or normal wear
Cedar lumber structural integrity	5 years from installation	Covers structural failure not caused by impact damage, settlement, or abnormal loading
Electrical rough-in	1 year from inspection sign-off	Per Ohio Residential Code; licensed electrician work
Gas rough-in	1 year from inspection sign-off	Per Ohio Gas Code; includes pressure test certification
Stain and sealant adhesion	2 years	Subject to maintenance application per manufacturer schedule (every 2-3 years)
Concrete work	5 years against structural cracking	Normal surface cracks excluded; covers settlement or heave-related cracking

Stain Maintenance Schedule: Cedar oil-based stain (Cabot Australian Timber Oil) should be reapplied every 2 to 3 years or when water no longer beads on the surface. First maintenance coat recommended 18 to 24 months after installation. Clean surface with mild soap and water before reapplication. Ironwood Outdoor Living LLC offers a maintenance service at \$650 per application.

Insurance and Licensing: Ohio Contractor License No. OHL-2008-88041. General liability insurance \$2,000,000 per occurrence, \$4,000,000 aggregate. Workers compensation coverage for all employees. Certificates available upon request. See x7.xlsx for home maintenance tracking upon project completion.