

WRITTEN ESTIMATE

Prepared for	Phil Patrick Lane	Estimate no.	HM-2026-BW
Property	127 Elm Hollow Road, Brattleboro, VT 05301	Date	2026-02-24
Phone	802-555-0188	Valid for	60 days
		Proposed start	2026-10-12

1. Scope of Work

Permanent repair of the leaking basement window on the north foundation wall. The existing single-pane wood window and frame have rotted at the sill, allowing water entry during heavy rain. Two temporary patches were made in 2024 and 2025; this estimate covers a full replacement and regrading of the window well. See the home maintenance log X06 for the patch history and the homeowners water-backup coverage in P02.

2. Itemized Estimate

Item	Description	Amount
Demolition	Remove rotted window, frame, and sill	\$95.00
Window unit	Glass block egress-style basement window	\$185.00
Framing and sill	Pressure-treated framing, new sill	\$140.00
Waterproofing	Membrane, flashing, sealant	\$90.00
Window well	Regrade and add gravel drainage	\$85.00
Labor	Approximately 7 hours	\$90.00
Total estimate		\$685.00

3. Terms

- This is an estimate, not a fixed-price contract; final cost may vary if hidden rot is found in the foundation framing.
- A deposit is not required; payment is due on completion.
- Materials carry the manufacturer warranty; labor is warranted for one year.
- Work to be scheduled for a dry-weather window in October 2026.
- Homeowner to clear access to the basement window area before the start date.

4. Timeline

Phase	Estimated Duration
Demolition and prep	Half day
Window install and framing	Half day
Waterproofing and well regrade	Half day
Cure and final check	Next dry day

Total on-site time is approximately one and a half working days, weather permitting. Sam will call to confirm the start date once the forecast is clear.

5. Notes from the Walk-Through

Sam inspected the window on February 24, 2026. The sill is soft to the touch and the lower frame shows water staining. The window well holds standing water after rain because the grade slopes toward the house. Regrading the well and adding gravel will move water away from the foundation and should resolve the recurring leak. A glass-block unit is recommended over wood for durability in this below-grade location.

6. Acceptance

To proceed, call Sam at 802-555-0850. This estimate is valid for sixty days from the date above. Phil plans to confirm scheduling for the October dry window after the heating-oil pre-buy is locked; see X12.

Homeowner signature and date

Sam Pereira, Pereira Home Repair

Appendix: Record Index and Notes

Contractor estimate for the basement window repair.

Related records

Code	Record	Where kept
X06	Home maintenance and repair log	Workbook
P02	Homeowners water-backup coverage	Insurance file
X12	Heating oil pre-buy timing	Workbook

Filing notes

- Estimate valid 60 days from February 24, 2026.
- Confirm the October dry-weather start date by phone with Sam.
- Clear access to the basement window well before the start.
- Record the final paid amount in the maintenance log X06.

This appendix is for the household's own record keeping. Document code P06. Retain with related papers; see the home inventory D05 for the full filing list.