

Kiln firing schedule notebook

Skutt KM 1027 electric kiln. Bisque schedule reference. Not for the Q3 close.

Bisque schedule (cone 04)

Segment	Ramp (F/hr)	Target (F)	Hold (min)	Note
Water smoke	100	200	30	moisture out
Preheat	150	500	0	steady climb
Body temp	250	1900	0	coming to bisque
Bisque final	150	1945	10	cone 04 hits
Cool down	off (natural)	ambient	12 to 18 hr	no crack

Glaze schedule (cone 6 for the electric batch, cone 10 for Tom's gas kiln)

For cone 6: preheat 250 F/hr to 250, then 400 F/hr to 2000, then 150 F/hr to 2232, hold 15 minutes. Natural cool.

For cone 10 at Tom Whitfield's studio: separate schedule, do not run in the home kiln. Reduction firing, gas, all day event.

Loading rules

Bisque loose: pieces can touch, not stack unglazed.
Glaze fired: no touching, half inch minimum between rims.
Kiln shelves washed with kiln wash before every glaze firing.
Cones set as witness, do not trust the controller alone.
Log every firing in the shelf book (Tom's studio has the ledger).

Reminders

Never fire without the exhaust vent running.
Do not open the kiln above 300 F unless it is an emergency.
Cedar stays in the bedroom on firing days.
Firing days are Tuesday or Saturday morning, not both.
Skip firing on Tahlequah weekends.

Craft reference. Not a task for the pottery close.